


FOUNDATION PLAN



LINTEL BEAM PLAN AND RC CANOPY PLAN

<p>F1</p> <p>SIZE: 1.50 X 1.50 X 0.35 M.</p> <p>REINFORCEMENTS: 10 - 16 MM Ø RSB BW</p> <p>DEPTH: 1.50 M. (VARIES)</p> <p>QUANTITY: 12 SETS</p>	<p>C1</p> <p>SIZE: 0.30 X 0.30 M.</p> <p>REINFORCEMENTS: 8-16 MM Ø VRSB</p> <p>LATERAL TIES: 10 MM Ø DEF RSB AT 0.20 MOC</p>	<p>SC1</p> <p>SIZE: 0.15 X 0.30 M.</p> <p>REINFORCEMENTS: 6-12 MM Ø VRSB</p> <p>LATERAL TIES: 10 MM Ø DEF RSB AT 0.20 MOC</p>	<p>WF1</p> <p>SECTION THROUGHOUT</p> <p>SCALE: 1:40 MTS</p>
--	---	--	--

DETAIL OF COLUMN FOOTING, COLUMN, STIFFENER COLUMN AND WALL-FOOTING 1

<p>C1</p> <p>SIZE: 0.30 X 0.30 M.</p> <p>REINFORCEMENTS: 8-16 MM Ø VRSB</p> <p>LATERAL TIES: 10 MM Ø DEF RSB AT 0.20 MOC</p>	<p>SC1</p> <p>SIZE: 0.15 X 0.30 M.</p> <p>REINFORCEMENTS: 6-12 MM Ø VRSB</p> <p>LATERAL TIES: 10 MM Ø DEF RSB AT 0.20 MOC</p>	<p>LB FOR WINDW, DOOR OPENING AND RC CANOPY</p> <p>SIZE: 0.15 X 0.30 M.</p> <p>REINFORCEMENTS: 4-12 MM Ø VRSB</p> <p>LATERAL TIES: 10 MM Ø DEF RSB AT 0.20 MOC</p>	<p>RC CANOPY SECTION DETAIL</p> <p>SIZE: 1.00 X 0.10 M.</p> <p>REINFORCEMENTS: 12 MM Ø DEF RSB AT 0.15 MOC BW</p>
---	--	---	--

DETAIL OF COLUMN, STIFFENER COLUMN, LINTEL BEAM AND RC CANOPY DETAIL



REPUBLIC OF THE PHILIPPINES
DEPARTMENT OF AGRICULTURE
PHILIPPINE RURAL DEVELOPMENT PROJECT
PROVINCE OF QUEZON



PROJECT TITLE :
**CONSTRUCTION OF
PINEAPPLE PROCESSING CENTER**
PROJECT LOCATION : BRGY. NIEVA GEN. LUNA, QUEZON

PREPARED AND SUBMITTED BY :

REVIEWED BY:

ROMARICO A. ALLAREY
ASSISTANT PROVINCIAL ENGINEER

RECOMMENDING APPROVAL

JOHNNY A. PASATIEMPO
PROVINCIAL ENGINEER

APPROVED :

HON. DANILO E. SUAREZ
GOVERNOR

SHEET CONTENT:

CAD BY:

DATE:

SHEET NO.

S-2-4-10-17

STRUCTURAL